

NOVEMBER 13, 2008

W.C. Carter
 NORTH CAROLINA
 PROFESSIONAL ENGINEER
 WAYNE CARTER
 0218

1007 Shepard Street
 Morehead City, North Carolina 28557
 Telephone: 252.247.2127 Fax: 252.247.0674
 Email: eda@eda.com

These drawings, specifications and notes are prepared by the firm of EDA, Inc. and are the property of EDA, Inc. The owner shall be permitted to use these drawings, specifications and notes for the project only. Any other use without the written consent of EDA, Inc. is prohibited. The drawings shall be published or otherwise made available to the public at the discretion of EDA, Inc.

Architects Engineers Planners
EDA pa

**CEDAR ISLAND FERRY
 OFFICE RENOVATION
 CEDAR ISLAND, NORTH CAROLINA**


08-046

2007412


ISSUED: 08-12-08
 DWG BY: MLR
 CKD BY: RMB, LDD

REVISIONS

SHEET NO.
E-2
 OF 3



**1 FLOOR PLAN - POWER
 E-2 SCALE: 3/16" = 1'-0"**



ALL BREAKERS 20 AMP/ 1 POLE UNLESS OTHERWISE NOTED.

PANEL-M	AIC : EXISTING		RATING: 500		3 PHASE 4 WIRE		MOUNTING: SURFACE		600A MAIN BREAKER		EQUIPMENT GROUND BUS		S.E. LABEL	
	WIRE	SIZE	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT
LOAD SERVICE	WIRE	SIZE	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT
NO LABEL														
NO LABEL														
HEAT PUMP CU1														
HEAT PUMP CU2														
EXIST. MAIN 2														
EXIST. MAIN 1														
BREAKER LOAD COMPUTED BASED ON 125% OF ALL LIGHTING LOADS, RECEPTACLE CIRCUITS AT 180 V-A/RECEPTACLE & H.V.A.C. LOADS BASED ON M.C.A. RATING OF EQUIPMENT														
* REPLACE EXISTING BREAKER														

ALL BREAKERS 20 AMP/ 1 POLE UNLESS OTHERWISE NOTED.

PANEL-PDP	AIC : EXISTING		RATING: 100		3 PHASE 4 WIRE		MOUNTING: SURFACE		NO MAIN BREAKER		EQUIPMENT GROUND BUS		S.E. LABEL	
	WIRE	SIZE	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT	FR	CKT
LIGHTING *														
LIGHTING *														
LIGHTING *														
LIGHTING *														
DED. QUADRAPLEX														
DED. QUADRAPLEX														
DED. QUADRAPLEX														
DED. QUADRAPLEX														
BREAKER LOAD COMPUTED BASED ON 125% OF ALL LIGHTING LOADS, RECEPTACLE CIRCUITS AT 180 V-A/RECEPTACLE & H.V.A.C. LOADS BASED ON M.C.A. RATING OF EQUIPMENT														
* CIRCUIT THRU TIMECLOCK														
** ADD NEW W/P OR RECEPTACLE AT CONDENSERS TO EXISTING CIRCUIT.														

WATTAGE SUMMARY

LIGHTING :	2,550 S.F. X 3 V-A/S.F. X 1.25	PANEL PDP1	9,563 V-A
TRACK LIGHTS	40 L.F. X 75 V-A/L.F.		3,000 V-A
RECEPTACLES :	13 @ 180 V-A/REC.		2,340 V-A
WATER HEATER:	(@ 125%)		5,625 V-A
SIGN CIRCUIT:			1,500 V-A
DED. RECEPTACLES:			4,500 V-A
H.V.A.C. :			
FANS :			756 V-A
HEATERS:			--
HEAT PUMPS:	(as per N.E.C. 430-25)		-----
			27,284 V-A
	27,284 V-A		
			= 75.8 AMPS
	208V X 1.732		